

REPLY TO PRE-BID QUERIES

BIDDING DOCUMENT NO. : MEC/23R8/01/51/D2/T03/ER/6523

SUBJECT OF BIDDING DOCUMENT : LAYING OF UNDER GROUND PE PIPE LINES AND ABOVEGROUND GI INSTALLATIONS INCLUDING LAST MILE CONNECTIVITY AT CONSUMER END AT VIJAYAWADA AND KAKINADA

Sl. No.	PART / Section / Clause No.	Page No.	Clause Description	Bidder's Query	Reply to Bidder's Query
1.	Part-III /Section-4 /Clause 4.2	17 of 31	Material to be Supplied by Contractor	We do not dig trench in open cut method in most of the areas as in city limits is not possible and its a very rare that we can open cut inside houses as there are several utilities and the house owner wouldn't permit too .In all the case as due to Nalla ,Road ,utilities or the permission are never such that we can lay MDPE pipe line in Continues manner, Hence Warning Mat has to cut into pieces and laid, Hence there is no use warning mat with tracing Wire and the procurement of the same is also difficult as there are very few Suppliers . In view of the above kindly see if the tracing wire is exempted and rest remains the same.	Tender conditions prevails.
2.	Part-III /Section-3 /Annexure -5 to SCC Clause Sl.No.1 and Part-III/Section-5 /SOR item no.1.1	39 of 53 and Page 1 of 12	Terms of payment /Laying of MDPE Pipes	In Payment terms and conditions its mentioned that 80% of the payment to be released on jointing. In that case no one will be willing to lay the 20 mm MDPE pipe line unless the 32/63 mm MDPE pipe is laid /Tested and Gas commissioned as in the present scenario this things are exempted and Contractors claim the 20 mm MDPE pipe line with even without Jointing.	As per SOR item No. 1.1, laying of the 32/63 mm MDPE is in the scope of contractor. Further, fronts will be given to successful bidders where the main MDPE pipeline network is available so that the entire work of the laying of the 20mm MDPE pipeline will be completed.

Sl. No.	PART / Section / Clause No.	Page No.	Clause Description	Bidder's Query	Reply to Bidder's Query
3.	Part-III/ Section-3 /Annexure -5 to SCC Clause Sl.No.11 and Part-III/Section-5 /SOR item no.11	40 of 53 and Page 7 of 12	Terms of payment /Laying of GI Pipes	In Page no 40 of 53, SOR no 11, Terms of Payments its mentioned 100 % of the GI Piping payment will be released on installation Testing, Submission of as-built drawings and material reconciliation and Submission of final bill or is it anyway related to Conversion of the Stove? Please clarify.	Refer Sl.No.18 (for SOR item no.22) page no. 41 of 53, Payment terms for the item Conversion of stove.

Note: This document shall form an integral part of the bidding document and shall be signed/stamped and submitted along with the bid.

(STAMP & SIGNATURE OF BIDDER)

Dated: 14.02.2020

CORRIGENDUM#1

TO

BIDDING DOCUMENT

BIDDING DOCUMENT NO. : MEC/23R8/01/51/D2/T03/ER/6523

SUBJECT OF BIDDING DOCUMENT : LAYING OF UNDER GROUND PE PIPE LINES AND ABOVEGROUND GI INSTALLATIONS INCLUDING LAST MILE CONNECTIVITY AT CONSUMER END AT VIJAYAWADA AND KAKINADA

The terms and conditions of the Bidding Document stands modified to the extent indicated below and all other terms and conditions of the Bidding Document remains unaltered:

Sn. No.	PART of Bidding Document	Section	Page No.	Clause No.	Clause Description	Additions / Deletions / Modifications
1.	PART-III	SECTION 5 - Schedule of Rates (SOR)	5 of 12	SOR Item no.7 for Vijayawada and Kakinada area	Includes cost of transportation, loading & unloading, Custody and labour for placing the bricks in trenches .	Shall be read as given below: "Supply and placing of Class 35 bricks in trenches as per the direction of EIC and as per specifications. Item includes cost of transportation, loading & unloading, Custody and labour for placing the bricks in trenches."
2.	PART-III	SECTION 5 - Schedule of Rates (SOR)	6 of 12	SOR Item no.9 for Kakinada area	Restoration of bitumen Asphalt road / concrete roads / pavements / foot paths after laying of MDPE pipe line as per specifications and instruction of Engineer-In-Charge. Restoration of roads shall be done to fullest satisfaction of Local Municipalities/Govt. Authorities / NHAI / , R&B etc. and to get NOC from the concerned	Shall be read as given below: "Restoration of bitumen Asphalt road / concrete roads / pavements / foot paths after laying of MDPE pipe line as per specifications and instruction of Engineer-In-Charge. Restoration of roads shall be done to fullest satisfaction of Local Municipalities/Govt. Authorities / NHAI / , R&B etc. and to get NOC from the concerned authorities/Society".

Sn. No.	PART of Bidding Document	Section	Page No.	Clause No.	Clause Description	Additions / Deletions / Modifications
3.	PART-III	SECTION 5 - Schedule of Rates (SOR)	7 of 12	SOR Item no.11 7 for Vijayawada and Kakinada area	installation of heavy duty GI pipes (as per IS:1239) at all floors alongwith supply and installation of all required fittings (approved make) such as sockets, elbow, tee, reducer, bend, union, GI plug, endcap etc, fixed vertically as well as horizontally for providing PNG connection to house hold in various type of Buildings including Highrise buildings. The scope also includes supply and installation of TF, wherever required. Item includes pneumatic testing of the assembled section as per the specification and standard procedure of testing of the complete installation, making required arrangement for fixing of the pipes such as scaffolding, rope ladder etc, supply and fixing of approved clamp, screw (SS screw of approved make), dowel plug, steel supports with rods, fastners etc. If required, making holes by core cutting etc and making good the holes with grout of the matching clour/shade also included. All threading shall be NPT threading with thread making machine. Only GI Pipes are Free issue material. All of the assembled section as per the specification and standard procedure of test	Shall be read as given below: "Installation of heavy duty GI pipes (as per IS:1239) at all floors along with supply and installation of all required fittings (approved make) such as sockets, elbow, tee, reducer, bend, union, GI plug, end cap etc, fixed vertically as well as horizontally for providing PNG connection to house hold in various type of Buildings including High-rise buildings. The scope also includes supply and installation of TF, wherever required. Item includes pneumatic testing of the assembled section as per the specification and standard procedure of testing of the complete installation, making required arrangement for fixing of the pipes such as scaffolding, rope ladder etc, supply and fixing of approved clamp, screw (SS screw of approved make), dowel plug, steel supports with rods, fasteners etc. If required, making holes by core cutting etc and making good the holes with grout of the matching colour/shade also included. All threading shall be NPT threading with thread making machine. Only GI Pipes are Free issue material. All GI pipe fittings and clamps, shall be powder coated of approved colour and shade."

Note: This Corrigendum shall form an integral part of the bidding document and shall be signed/stamped and submitted along with the bid.

(STAMP & SIGNATURE OF BIDDER)